



## NOTES:

- 1. STAKES SPACED @ 8' MAX.
- 2. USE 2" x 2" (±3/8) X 48" WOOD OR EQUIVALENT STEEL STAKES. STAKE DIMENSIONS ARE ACTUAL (NOT NOMINAL).
- 3. FILTER FABRIC FENCE MUST BE PLACED AT LEVEL EXISTING GRADE. BOTH ENDS OF THE BARRIER MUST BE EXTENDED AT LEAST 8 FEET UPSLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT.
- 4. SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/2 THE ABOVE GROUND HEIGHT OF THE FENCE.
- 5. ANY SECTION OF FILTER FABRIC FENCE WHICH HAS BEEN UNDERMINED OR TOPPED MUST BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET. SEE STANDARD CONSTRUCTION DETAIL #18.

	01	STANDARD CONSTRUCTION DETAIL
L		#20 REINFORCED FILTER FABRIC FENCE
	0704	1 #20 KLINI OKOLD I ILTLK I ADKIG I LNOU
- 1	C701	(30" HIGH)





## MAINTENANCE:

- 1. THE STRUCTURE'S THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK.
- 2. A STOCKPILE OF ROCK MATERIAL SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE.
- 3. AT THE END OF EACH CONSTRUCTION DAY, ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION

02	STANDARD CONSTRUCTION DETAIL
C701	#16 ROCK CONSTRUCTION ENTRANCE

## MAINTENANCE SCHEDULE

CONTROL MEASURE	INSPECT	PROBLEMS TO LOOK FOR	POSSIBLE REMEDIES
VEGETATION	WEEKLY AND AFTER EVERY RUNOFF EVENT	SEDIMENT AT TOE OF SLOPE RILLS AND GULLIES FORMING BARE SOIL PATCHES	CHECK FOR TOP-OF-SLOPE DIVERSION AND INSTALL IF NEEDED. FILL RILLS AND REGRADE GULLIED SLOPES. RESEED, FERTILIZE, AND MULCH BARE AREAS.
ROADSIDE DITCH	WEEKLY AND AFTER EVERY RUNOFF EVENT	CHANNEL CONFIGURATION DOES NOT MEET DESIGN CONFIGURATION	REGRADE CHANNEL TO DESIGN CONFIGURATION REGRADE FOR POSITIVE SLOPE
ROCK CONSTRUCTION ENTRANCE	WEEKLY AND AFTER EVERY RUNOFF EVENT	SINK HOLES OR RUTS SEDIMENT ON PUBLIC ROADWAY	ADD ROCK TO BRING TO SPECIFIED DIMENSIONS. SWEEP MATERIAL BACK TO PROJECT SITE. DO NOT WASH ROADWAY WITH WATER.
FILTER FABRIC FENCE	WEEKLY AND AFTER EVERY RUNOFF EVENT	UNDERCUTTING OF FENCE FENCE COLLAPSING  TORN FABRIC  RUNOFF ESCAPING AROUND BARRIER  SEDIMENT LEVEL NEAR TOP OF FENCE	REPLACE FAILED SECTION WITH ROCK FILTER OUTLET  CHECK FENCE POST SIZE AND SPACING, GAUGE OF WIRE MESH, AND FABRIC STRENGTH. CHECK DRAINAGE AREA, SLOPE LENGTH, AND GRADIENT BEHIND BARRIER. CORRECT ANY SUBSTANDARD CONDITION. REPLACE WITH CONTINUOUS PIECE OF FABRIC FROM POST TO POST. SECURELY ANCHOR WITH PROPER STAPLES.  EXTEND FENCE. REMOVE SEDIMENT WHEN LEVEL REACHES HALF OF FENCE HEIGHT.

THE PERMITTEE SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF ALL TEMPORARY CONTROL MEASURES DURING CONSTRUCTION. ALL DEVICES SHOULD BE INSPECTED WEEKLY AND AFTER EVERY RUNOFF EVENT. IF DURING THESE INSPECTIONS, ANY DEVICE IS FOUND TO BE CLOGGED, DAMAGED, HALF-FULL OF SILT OR NOT FULLY OPERATIONAL, THE DEVICE(S) SHALL BE CLEANED OF ALL DEBRIS. ALL REPAIRS MUST BE COMPLETED WITHIN 72 HOURS OF DISCOVERY


UPON COMPLETION OF THE PROJECT, RECYCLING OR DISPOSAL OF ALL TEMPORARY EROSION CONTROL MATERIALS SHALL BE THE RESPONSIBILITY OF THE EARTHMOVING CONTRACTOR. CONSTRUCTION WASTE INCLUDES, BUT IS NOT LIMITED TO, EXCESS SOIL MATERIALS, SILT REMOVED FROM EROSION CONTROL FACILITIES, EXCESS BUILDING MATERIALS, CONCRETE WASH WATER, SANITARY WASTES, AND OBSOLETE EROSION CONTROL MATERIALS (SILT FENCE, SILT SACKS, ETC.).

SILT REMOVED FROM SEDIMENT CONTROL FACILITIES SHALL BE SPREAD ON THE TOPSOIL STOCKPILE, OR IN LAWN OR LANDSCAPE AREAS. OBSOLETE EROSION CONTROL MATERIALS AND EXCESS BUILDING MATERIALS MUST BE DISPOSED OF AT A DEP APPROVED SITE.

03	MAINTENANCE SCHEDULE
C701	I WAIN I ENANCE SCHEDULE



PE-082447



S Ш

MANOR

SUCKINGHAI ANDY LAKE TOWNSHIP ERCER COUNTY, PA CONSTRUCTION **DETAILS** 

Project Number: <u>C-19515-0001</u> Drawing Scale: N.T.S. Date Issued: JAN 2023 Index Number: --Drawn By: SMS Checked By: KRH Project Manager: KRH

C701